

15-195-21044-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,044-00-00

LEASE NAME Rayzak #1

WELL NUMBER

SPOT LOCATION SE NW SW

SEC. 22 TWP. 11 RGE. 21W(E) or (W)

COUNTY Trego

Date Well Completed

Plugging Commenced 12/6/84

Plugging Completed 12/10/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Beren Corporation

ADDRESS 970 4th Finan. Ctr. Wichita, Ks. 67202

PHONE # () OPERATORS LICENSE NO. 5364

Character of Well
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 3962'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8 | 317' | none |
| | | | | 5 1/2" | 3961' | 2717' |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set.

Plugged bottom with 5 sacks cement, sand to 3875' & 5 sacks cement. Shot pipe at 3000', & 2717'. Pulled 68 joints of pipe. Plugged well with 6 hulls, 25 gel, & 200 sacks 50/50 poz 8% gel.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

RECEIVED

STATE CORPORATION COMMISSION


STATE OF Kansas COUNTY OF Rice, ss.

1-4-1985
JAN 04 1985

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
(Address) Box 347, Chase, ks. 67524

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1984



[Signature]
Notary Public

My Commission expires:

15-195-21044-00-00

DAILY DRILLING REPORT

BEREXCO INC.

PROSPECT Razak YEAR 1982 1650' fsl & 990' fwl
LEASE Razak WELL NO. 1 WELL LOCATION SE NW SW COUNTY Trego STATE KS
WELL SITE LEASE DESCRIPTION Sec. 22-11S-21W API# 15-195-21,044-00-00

OPERATOR BEREXCO INC.
CONTRACTOR Strata Drilling
GEOLOGIST Tony Kruse
DEVELOPMENT WELL PROSPECT TEST WELL X
OWNERSHIP 1982 BEREXCO Program

ELEVATION: GR 2272'
DF _____
KB 2277'

NOTIFY _____

IDENTIFICATION Test Well

TOPS:
Anhydrite 1725 (+552)
Base Anhydrite 1779 (+498)
Topeka 3328 (-1051)
Heeb 3540 (-1263)
Toronto 3560 (-1283)
LKC 3577 (-1300)
Marmaton 3868 (-1591)
Arbuckle 3902 (-1625)

RECEIVED
STATE COMMISSION
NOV 05 1982
CONSULTATION DIVISION
Wichita, Kansas

3962 (-1685)

MOVING IN & RIGGING UP 7/12/82 SPUD 7/12/82

SET 8 5/8 @ 317' w/ 200sx. 60/40 poz.

| DATE | DEPTH | DST |
|---------|---------------------------|--|
| 7/13/82 | 520' | #1 3352 - 3372 30/30/30/30 25' mdy wtr. |
| 7/14/82 | 2460' | 1136/1082 43/43 43/43 |
| 7/15/82 | 3275' | #2 3907 - 3962 (Arb) 60/60/60/60 |
| 7/16/82 | 3628' | 65' oil + 450' SOC mdy wtr + 540' SO specked wtr |
| 7/17/82 | 3962' RTD | 1136/1093 65/393 436/534 |
| | Set 5 1/2" @ 3961', 1' OB | #3 3890 - 3938 (Arb straddle) 60/60/60/60 |
| | | 85' oil + 180' OCM (20% oil) 1040/982 54/65 109/109 |

LOG TOPS:
Anhydrite 1728 (+ 549)
Base Anhydrite 1775 (+ 502)
Topeka 3333 (-1056)
Heebner 3543 (-1266)
Toronto 3568 (-1291)
Lansing 3582 (-1305) +6
BKC 3816 (-1539)
Marmaton 3872 (-1595)
Arbuckle 3901 (-1624) +37
LTD 3960 (-1683)