

15-051-03693-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 137-15

LOCATION NE NE NE

SEC. 3 TWP. 11 RGE. 17

Dry Hole  Abandoned Oil Well  Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Simpson 420 W. Douglas

Operator The Derby Oil Co Address Wichita, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3690 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 162' circulated with cement - 5 1/2" at 3668' with 100  
sax cement behind - Lane Wells plugs at 3620', perforated at  
3573'.

Sand to 3560', set 4 sax cement with dump bailer, pulled 3085'  
5 1/2", mud to 162', set rock and 15 sax cement, mud to 35', set  
rock and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 2 1953  
CONSERVATION DIVISION  
Wichita, Kansas

Eldon Perry  
District Conservation Agent

Date ~~10-31~~ 10-31-53

PLUGGING  
FILE SEC. 3 T 11 R 17  
BOOK PAGE 132 LINE 15