

KANSAS

FORM CP-3  
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-051-22,993-00-00 ✓

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name Liberty Enterprises, Inc.

Complete Address 308 W. Mill, Plainville, Ks. 67663

Lease Name Simpson "A" Well No. 2

Location C-W/2 NW SW Sec. 3 Twp. 11 Rge. 17 (East) (West)

County Ellis Total Depth 3510'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pioneer Drilling Co., Inc.

Address 308 W. Mill, Plainville, Ks. 67663 License No. \_\_\_\_\_

Operation Completed: Hour: 4:00 AM Day: 30 Month: 4 Year: 19 82

Plugging Operations attended by Agent?: All xxxxx Part \_\_\_\_\_ None \_\_\_\_\_

The above well was plugged as follows:

8 5/8"-225' S.P. Cmc. w/150 sacks common-2% Gel.-3% Cal.Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem W/heavy mud between all plugs.

1st plug @ 750' w/70 sacks cement

2nd plug @ 240' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 225' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: \_\_\_\_\_  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION

MAY 3 1982  
5-3-1982  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICE

DATE 5-14-82  
DATE \_\_\_\_\_  
INVOICE No. 164-W