

15-051-05627-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 121-8
610' N of S line & 990' W of East line
LOCATION _____
of SE 1/4
SEC. 12TWP. 11 RGE. 17

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease Cress Box 544

Operator Gulf Oil Corp. Address Chase, Kans

Field _____ County Ellis

Total Depth 3303 Feet.

Plugging Contractor Morgan Well Plugging

Plugging Contractor's License No. 43

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 983' 575 sax cement behind - 5 1/2" at 3300' with
115 sax cement behind.

Sand to 3290', set 4 sax cement with dump bailer, pulled
2675' 5 1/2" - pumped hole full mud - 30 sax Halcogel - pumped
cementing plug to 300' followed by 100' sax cement filling
hole from 300' to 0' with cement.

Mudding and cementing by Halliburton Co. 500# pump pressure.

[Signature]
District Conservation Agent

Date 8-22-53

RECEIVED
STATE CORPORATION COMMISSION
8-26-1953
AUG 26 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 12 T 11 R 17 W
BOOK PAGE 121 LINE 8