

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-12-1960
OCT 12 1960
CONSERVATION DIVISION
Wichita, Kansas

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: Ellis
Location: SE NE SW Sec. 30 Twp. 11 Rge. 17 (E) (W)
Name of Field: _____ Total Depth: 3655

I have this date completed supervision of plugging of:

Lease Name: Peavy Well No. 4
Operator's Full Name: Walters Drg Co
Complete Address: 510 Orpheum Bldg Wichita, Kans
Plugging Contractor: Ace Pipe Pulling Co
Address: Great Bend, Kans License No. 2
Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____
Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No
If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 5 Month 10 Year 60

The above well was plugged as follows:

8 5/8" 191' circulated with cement - 5 1/2" 3652' with 100 sax cement, squeezed at 850' with 300 sax cement.

Filled with sand to 3640', set 4 sax cement with dump bailer, started 545' 5 1/2" - circulated hole with heavy mud (Gel) through 5 1/2" at 545', displaced 20 sax cement through 5 1/2" at 545', heavy mud to 200', displaced 20 sax cement through 5 1/2" at 200', heavy mud to 35', set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by Sun Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 10/31/60
INV. NO. 2118-w