

15-051-00786-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW NW NE

SEC. 30 TWP 11 RGE. 17W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Hadley "B" 510 Orpheum Bldg

Operator Walters Drg Co Address Wichita, Kans

Field _____ County Ellis

Total Depth 3676 Feet.

Plugging Contractor R & D Casing Pulling Co & Globe Cementing Co

Plugging Contractor's License No. 737

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 191' circulated with cement - 5 1/2" at 3652' with
100 sax cement behind - P.B. cement and Lane Wells plugs to
3639' - perforated at 3632'.

Sand to 3620', set 4 sax cement with dump bailer, pulled
approx 3000' 5 1/2", pumped hole full mud (25 sax commercial
mud) pumped cementing plug to 190', followed by 60 sax
cement - Cement 190' to 0' - Cementing and mudding by
Globe cementing Co.

RECEIVED
STATE CORPORATION COMMISSION
8-16-1954
AUG 16 1954
CONSERVATION DIVISION
Wichita, Kansas

E. J. [Signature]
District Conservation Agent
Date 8-11-54

PLUGGING
FILE SEC 30 T 11 R 17W
BOOK PAGE 56 LINE 41