

15-051-04825-00-00

Form CP-3

KANSAS

Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-27-1972
APR 27 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlim Petroleum Company

Complete Address Box 308 Ellinwood, Kansas 67526

Lease Name Hadley "L" Well No. 5

Location C W/2 SW SE Sec. 30 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3648'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Tools by HOWCO

Address License No.

Operation Completed: Hour 12 N Day 26 Month 4 Year 1972

The above well was plugged as follows:

Total Depth 3648' 10 3/4 csg set at 160' cwc

5 1/2 csg set at 3630' cw 200 sk cmt.

5 1/2 csg perf. (3605-3624)

5 1/2 csg squeezed at 970' W/200 sk cmt. No pipe recovered.

Ran 104 jts tbg set at 3175' -pumped 25 sk gel & water W/100 lbs hulls, -displaced

25 sk cmt. Pulled 84 jts tbg set at 600' -circ 60 sk cmt to surface. Pulled

remaining 20 jts tbg and capped 5 1/2 csg W/5 sk cmt.

Pumped 10 sk cmt down anulus with 100 lbs pres.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 5-3-72

INV. NO. 5650-W