

15-051-05168-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1975
3-24-1975
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Champlin Petroleum Company

Complete Address 6051 N. Brookline, Suite 116, Oklahoma City, Oklahoma 73112

Lease Name Hadley "L" Well No. 6

Location SW NW SE Sec. 30 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3630'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 12:30 P Day 19 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 3630' 8 5/8 csg set 225' cwc 150 sk.

5 1/2 csg set 3630' cw 175 sk cem.

5 1/2 csg PBD 3611' & perf. 3507-3509) PB 3518' & Perf. (3320-3337)

PB 3314 & PFS (3294-3301)

Filled 5 1/2 csg W/snd (3314-3275) dmped 4 sk cem W/dump bailer. (3275-3245)

Cutoff & recovered 2654' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg W/70 sk Lt. Cem. -28 sk gel & water -released plug

& capped with 50 sk Lt. Cem. by Halliburton. PP 300 lbs. SIP 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rich T. Massey
Well Plugging Supervisor

DATE 3/26/75

INV. NO. 1044-W