

15-051-04827-00-00

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NW SE SW

SEC. 30 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 21 Lease Peavy Peavy

Operator El Dorado Refg Co Address El Dorado, Kans

Field Bemis County Ellis

Total Depth 3663 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1358' circulated with 500 sax cement - 5 1/2" at 3637  
with 75 sax cement behind.

Filled with sand to 3625', set 4 sax cement with dump bailer,  
pulled 2950' 5 1/2", filled hole with mud to 300', set rock bridge  
and 15 sax cement, filled with mud to 35', set rock and 10 sax  
cement to bottom cellar.

**PLUGGING**  
FILE SEC 30 T 11 R 17  
BOOK PAGE 107 LINE 38

*E. Peavy*  
District Conservation Agent

Date 10-3-51

10-4-1951  
OCT X 4 1951  
CONSERVATION DIVISION  
Wichita, Kansas