

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 120-36  
LOCATION NW SW SE  
SEC. 35 TWP. 11 RGE. 17

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. B-1 Lease Morganstern - Spector Hall "D"

Operator Russell, Kans Address Russell, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3635 Feet.

Plugging Contractor Arnett Pipe Pulling

Plugging Contractor's License No. 265

Address \_\_\_\_\_  
(Describe briefly the manner in which the well was plugged)

8 5/8" at 1285' circulated with cement - 5 1/2" at 3602' with  
125 sax cement behind.

Sand to 3590' set 4 sax cement with dump bailer - pulled 2790'

5 1/2" - pumped hole full mud ( 25 sax Aquagel) set cementing

plug and rock bridge at 250' - ~~xx~~ set 20 sax cement at 250',

mud to 35', set rock and 10 sax cement to bottom cellar.

Edward [Signature]  
District Conservation Agent

Date 6-9-1955

**RECEIVED**  
STATE CORPORATION COMMISSION  
6-9-1955  
JUN 9 - 1955

CONSERVATION DIVISION  
Wichita, Kansas

**PLUGGING**  
FILE SEC 35 T 11 R 17W  
BOOK PAGE 120 LINE 36