

15-051-20524-00-00

Form CP-3
Rev. 6-4-68

KANSAS

AP
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-29-1971
MAR 29 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beacon Resources Corporation

Complete Address 1000 Century Plaza Wichita, Kansas 67202

Lease Name Hall "A" Well No. 1

Location SE SW SE Sec. 35 Twp. 11 Rge. (E) (W) 17

County Ellis Total Depth 3725'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486 Ellinwood, Kansas License No. 462

Operation Completed: Hour 12:30 P Day 27 Month 3 Year 1971

The above well was plugged as follows:

Total Depth 3725' 8 5/8 csg set at 252' cwc 160 sk.

5 1/2 csg set at 3614' cw 125 sk cmt.

5 1/2 csg PBTD 3450' with top perf. (3435)

Filled 5 1/2 csg W/sd (3400-3450) Dumped 5 sk cmt W/dump bailer. (3365-3400)

Cutoff and recovered 1976' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls -70 sk 50-50 poz cmt

W/4% added gel -7 sk gel -release plug and pumped 50 sk 50-50 poz cmt W/4% added gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Leo P. Messing*
Well Plugging Supervisor

DATE 3/31/71

INV. NO. 3467-W