

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-015 -22, 764-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Okmar Oil Co.

Complete Address 970 Fourth Financial Center, Wichita, Ks. 67202

Lease Name Hall Well No. 2

Location NESE SW Sec. 35 Twp. 11 Rge. 17 (East) (West)

County Ellis Total Depth 3600'

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXX

Other well as hereinafter indicated _____

Plugging Contractor Pioneer Drilling Co.

Address 308 W. Mill, Planville, Ks. 67663 License No. _____

Operation Completed: Hour: 2:30 PM Day: 23 Month: Jan. Year: 19 82

Plugging Operations attended by Agent?: All XXX Part _____ None _____

The above well was plugged as follows:

8 5/8" 290' S.P. cuc. W/ 160 sacks common 2% Gel. 3% Cal.Cl.

Ordered 130 sacks 50/50 posmix 4% Gel-3%Cal.Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 750' W/ 70 sacks cement

2nd plug @ 270' W/ 40 sacks cement

3rd plug solid bridge of hulls and plug @ 40' W/ 10 sacks cement.

Circulate 10 sacks in rat hole.

Amount of Surface Casing: 290' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

INVOICED

DATE

2-3-82

INV. NO.

9188-W

RECEIVED
STATE CORPORATION COMMISSION
1-25-1982
JAN 25 1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____

Conservation Division Agent