

*B*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 27-25  
LOCATION SE SE SW  
SEC. 35 TWP. 11 RGE. 17W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. B-2 Lease \_\_\_\_\_ Hall \_\_\_\_\_

Operator Forbes Casing Pulling Co. Address Box 221 Great Bend, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3630 Feet.

Plugging Contractor \_\_\_\_\_ same

Plugging Contractor's License No. 49

Address \_\_\_\_\_

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1316' circulated with 425 sax cement - 5 1/2" at

3626' with 125 sax cement behind.

Set 6 sax cement on bottom with dump bailer - pulled 2630' 5 1/2" -

filled with mud to 300', set rock and 20 sax cement, mud to

40', set rock and 10 sax cement to bottom cellar.

STATE CORPORATION  
JAN 7 - 1956  
1-7-1956  
CONSERVATION DIVISION  
Wichita, Kansas

*Edon Perry*  
District Conservation Agent

Date 1-4-56

PLUGGING  
FILE SEC. 35T 11R 17W  
BOOK PAGE 27 LINE 25