

11-26

292  
P

6031469

API NUMBER 15- 605-22,603-00-00  
C. W/2 NE, NE SEC. 36, T 10 S, R 25 W/Ex

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

4620 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3736

Lease Name Pfeifer Well # 1

Operator: R L T Investment

County Graham 131.13

Name & Address: St. Peter Rt.

Well Total Depth 4035 feet

Morland, Ks. 67650

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 204

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor B. J. Titan License Number

Address Oakley, Ks.

Company to plug at: Hour: PM Day: 26 Month: Nov Year: 19 90

Plugging proposal received from Randall

(company name) R. L. T. Inv. (phone)

were: 8 5/8 set at 204 cwc. Circ hole w/no less than 36 vis. mud w/no loss or gain

of fluid. Keep hole full and balance plugs w/mud. Order 190 sks 60/40 poz 6% gel 3% cc.

B. J.. Titan Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 6:45PM Day: 26 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe w/25 sks at 2100

100 sks at 1175 w/hulls

40 sks at 250

10 sks at 40 w/dp

Circ 15 sks in rathole.

Remarks: Anhy 2083 - 2116. Elev. 2433

(if additional description is necessary, use BACK of this form.)

RECEIVED  
JAN 4 1991  
01-04-1991  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 1-16-91

INV. NO. 30504

Jib.S.

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow