

4 060050

1-21

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-193-20,500-00-00
NW NE, SEC. 5, T 10 S, R 33 W/EX
4950 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020
Operator: Rine Exploration Company
Name & Address: 300 W. Douglas, Suite 645
Wichita, KS 67202-5418

Lease Name Carpenter Well # 1-5
County Thomas 155.35
Well Total Depth 4780 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 327

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A xxxxxx

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Co. License Number 5422
Address Wichita, KS

Company to plug at: Hour: 7:00AM Day: 21 Month: January Year: 19 90

Plugging proposal received from Harold Maley
(company name) Abercrombie Drilling Co. (phone) 316-262-1841

were: Space all plugs through drill pipe with heavy drilling mud.

Order 190 sxs. 60/40 pos 6%gel 1/4# flocel per sx.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None xxxxxxxx
Operations Completed: Hour: 7:00AM Day: 21 Month: January Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2730' with 25 sxs. Anhydrite 2704-2755'
2nd plug at 1775' with 100 sxs. Dakota 1474-1774'
3rd plug at 375' with 40 sxs. Surface pipe to 327'
4th plug at 40' with 10 sxs. wiper plug at 40'
rathole with 15 sxs.

Arbuckle not reached. 02-14-1990

Remarks: B-J Titan
(If additional description is necessary, use BACK of this form.)

FEB 14 1990
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 2-16-90
INV. NO. 27477

Herb S.

Signed [Signature]
(TECHNICIAN)

Herb Deines