

4-031970

R 25

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-193-20,609-00-00

SE SE NE /4 SEC. 07 , 10 S, 33 W  
2970 feet from S section line  
330 feet from E section line

Operator license# 9482 Lease Baptist Church well # 1

Operator: National Petroleum Reserves, Inc. County Thomas

Address: 250 N. Rock Road Well total depth 4758 feet  
Suite #340 Conductor Pipe: 0 inch @ 0 feet  
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 331 feet

154.64

Aband. oil well  , Gas well  , Input well  , SWD  , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: A.M. Day: 25 Month: August Year: 94

Plugging proposal received from: Richard

Company: Kelso Casing, Inc. Phone: \_\_\_\_\_

Were: Order 350 sxs. 60/40 pozmix - 10% gel - 500# hulls.  
Halliburton Cement Company.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 9:00A.M., Day: 25, Month: August, Year: 94

Actual plugging report: 8 5/8" set @ 331' w/NA sxs. 5 1/2" set @ 4751'  
w/NA sxs. Perfs. 4207' - 4209'. D.V. 2700' w/365 sxs. cwc. Mixed and  
pumped 5 1/2" w/325 sxs. cement blend with 500# hulls to Max. P.S.I.  
700#. Close in P.S.I. 100#. Test backside to Max. P.S.I. 300# with 8  
sxs. Plug complete.

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD  BAD  Anhy. plug: YES  NO   
Bottom plug(in place): YES  , CALC  , NO  Dakota plug: YES  , NO   
Plugged through TUBING \_\_\_\_\_ , CASING  . Elevation: \_\_\_\_\_ GL

I did  / did not  observe the plugging. Carl Goodrow

DATE 9-12-94  
INV. NO. 41205

(agent)  
Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 09 1994  
09-09-1994  
CONSERVATION DIVISION  
WICHITA, KANSAS