

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20079-00-01
Spot: CSWSW Sec/Twnshp/Rge: 9-10S-33W
550 feet from S Section Line, 4730 feet from E Section Line
Lease/Unit Name: NOLLETTE Well Number: 1-9
County: THOMAS Total Vertical Depth: 4822 feet

Operator License No.: 6569
Op Name: SCHMITT, CARMEN, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

Conductor Pipe: Size feet: 8 1/2
Surface Casing: Size 8.625 feet: 363 250 SX CMT
Production: Size 4.5 feet: 4488 145 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 01/03/2003 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: EDWARD S. NEMNICH Company: CARMEN SCHMITT, INC. Phone: (620) 587-3361

Proposed Plugging Method: Ordered 425 sxs 60/40 pozmix - 600# hulls.
Plug through 4 1/2" casing.

Plugging Proposal Received By: HERB DEINES
Date/Time Plugging Completed: 01/03/2003 1:15 PM

WitnessType: Plugging Operations 100% Witnessed (Complete)
KCC Agent: DARREL DIPMAN

Actual Plugging Report:

BP at 4346'. PBTB 4434'.
Perforations @ 4352'-4358'; 4327'-4332'; 4310'-4314';
8 5/8" set at 363' - circulated with 250 sxs cement.
4 1/2" set at 4488' - cemented with 145 sxs cement.
Connected to 8 5/8" surface pipe.
Pumped 500# hulls and 160 sxs cement.
Max. P.S.I. 400#. S.I.P. 100#.
Connected to 4 1/2" casing.
Pumped 100# hulls and 215 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

RECEIVED
JAN 13 2003
KCC WICHITA
01-13-2003

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Darrel Dipman

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 1-14-03

NO. 2003061074

JAN 06 2003

#1-9 NOLLETTE "OWWO"

PRATHER OIL CORPORATION 9-10-33W
 418 PETROLEUM BLDG. #1-9 NOLLETTE "OWWO" 150' SW
 AMARILLO, TX 79101 C SW SW
 CONTR MURFIN DR LG. CO. CTY THOMAS

GEOL _____ FIELD WC 1/4 NW OF NOLLETTE;
 OVER 1 MI FROM PROD)

+	+	+
+	+	+
+	+	+

 ELV 3183 KB SPD 11/15/83 CARD ISSUED 4/12/84 IP P 20 BO & 10 BWPD
 LKC 4310-4332 OA

API 15-193-20,079-A

LOG	Top	Depth	Datum	OLD INFO: OPERATOR WAS DONALD C. SLAWSON & PETRO- LEUM, INC. #1 'M' NOLLETTE, SPD 5'15"76, SET B 5'8" 363' 250SX, (CARD ISSUED 6-9-76), CONTR: SLAWSON DRILLING CO., INC., GEOL. GEORGE MUELLER
ANH	2693+	490	DST (1) 4284-4320 (LKC) : 30-45-45-60, REC 5' MDY OIL, 125' HOCM, SIP 1264-1211#, FP 35-70 / 70-68#
B:ANH	2722+	461	DST (2) 4319-4347 (LKC) : PKR FAILED
HEEB	4082-	899	DST (3) 4317-47 (LKC) : PKR FAILED
LANS	4123-	940	DST (4) 4314-47 (LKC) : 30-45-30-60, REC 10' M W / SPTS OIL, SIP NA, FP 25-35#
STARK SH	4341-	1158	DST (5) 4340-72 (STARK SH) : 30-45-30-60, REC 30' SOCM, SIP 1089-440#, FP 26-35 / 35-53#
BKC	4400-	1217	DST (6) 4608-4695 (MARM) : 30-45-45-60, REC 20' M, SIP 173- 95#, FP 55-78 / 78-78#
MARM	4422-	1239	CORRECTION: 6-23-76 - ORIGINALLY FIRST REPORTED IN C SW SW
L:CHER	4615-	1432	
B:CHER	4710-	1527	
MISS	4721-	1538	
LTD&RTD	4822-	1639	

PRATHER OIL CORPORATION #1-9 NOLETTE "OWWO" 9-10-33W
 150' SW, C SW SW

NEW INFO: FR 10/14/83, RE-ENTERED 11/15/83, WSH DWN TO 4488, SET 4 1/2 " 4488, MICT - CO, PF (LKC)
 4352-58, AC 2000G (15%), SWB DWN, SO, NON-COMMERCIAL, SET BP AT 4346, PF (LKC) 4327-32 & 4310-
 14, ACIDIZED (AMT NA), SWB DWN, ALL PFS COMMUNICATED, BAD CMT JOB, SQ'D PFS W/CMT, RE-PF
 (LKC) 4327-32 & 4310-14, AC 3000G (15%), SWB DWN, GSO, POP, P APPX 20 BO & 10 BWPD

872312