

6 030454

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-193-20119-00-00

NWNW SEC. 5, T 10 S, R 34 W

4620 feet from M section line

4620 feet from W section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name DELORIS Well # 1

Operator: BERAN CORPORATION

County THOMAS 160.88

Name & Address 970 4TH FINANCIAL CTR.

Well Total Depth 4950 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67202

Surface Casing: Size 8 5/8 feet 336

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor KELSO CASING PULLING License Number 6050

Address BOX 347 CHASE KANSAS 67524

Company to plug at: Hour: PM Day: 24 Month: 5 Year: 19 85

Plugging proposal received from RONNIE

(company name) KELSO CASING (phone) _____

were: 8 5/8 SET @ 336' w/250 SX. 4 1/2" SET @ 4485 w/200 SX. PERF @ 4396-98' 4351-62'

ORDER SAND COM. CEM. PLUG BOTTOM, SHOOT OFF PIPE, STRIP PIPE. RECOVERED 2700'

ORDER 180 SX. 50/50 PZ 6" GEL 3" CCL 40 SX. GEL 4" SX. HULLS 8 5/8 W.P. SUN CEM.

WELL BACK WATER TRUCKS.

Plugging Proposal Received by Carl Goodlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45 PM Day: 24 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT BOTTOM PLUG 4" BAILER 4 SX. COM. CEM. SAND TO 4275 w/ BAILER

4 SX. COM. CEM. ON SAND TOP PLUG. Pump DOWN 8 5/8 w/ 4 SX. HULLS, 10 SX. GEL. 100 SX.

CEM. MIX. 30 SX. GEL. 8 5/8 W.P. 80 SX. CEM. MIX. MAX. PSE 300* CLOSE IN 150*

PLUG. COMPLETE

Remarks: _____
(if additional description is necessary, use BACK of _____)

INVOICED
did (or) observe this plugging.

DATE 6-8-85

Signed Carl Goodlow
(TECHNICIAN)

INV. NO. 8410

RECEIVED
STATE CORPORATION COMMISSION
06-05-1985
JUN 05 1985
CONSERVATION DIVISION
Wichita, Kansas