

6-28

4-071053

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-167-23,061-00-00

NE SE SE /4 SEC. 13, 11 S, 15 W  
990 feet from S section line  
405 feet from E section line

Operator license# 5886

Lease Schmeidler well #1-13

Operator: Chief Drilling, Inc.

County Russell 105.95

Address: 120 S. Market  
Suite #300  
Wichita, Kansas 67202

Well total depth 3260 feet  
Conductor Pipe: 0 inch @ 207 feet  
Surface pipe 8 5/8 Inch @ \_\_\_\_\_ feet

Aband. oil well \_\_\_\_, Gas well \_\_\_\_, Input well \_\_\_\_, SWD \_\_\_\_, D & A X

Plugging contractor: L.D. Drilling - Allied Cement License# \_\_\_\_\_

Address: Great Bend, Kansas 67530 - Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 28 Month: June Year: 93

Plugging proposal received from: Greg Dandson

Company: L.D. Drilling Phone: -

Were: 8 5/8" - 207' S.P. cwc. with 140 sx. 60/40 pozmix - 2% gel. - 3% c.c. By Allied Cement. Elv. 1799' - Anhy. 935' - No Arbuckle (3260 T.D.) Proposal 150 sx. 60/40 pozmix - 6% gel. and 1 sx. flocele. Spot and displace all cement through drill pipe. Heavy mud between all plugs - mud condition - Vis. 44 - Weight 9.4 - Viscosity 12. 25 sx. @ 945' - 100 sx. cement @ 475' w/1 sx. flocele - 10 sx. @ 40' - 15 sx. in rathole (circulate)

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 11:30A.M., Day: 28, Month: June, Year: 93

Actual plugging report: Chief Drilling ordered 150 sx. 60/40 pozmix - 6% gel. - circulated hole - spotted and displaced all cement through tubing with heavy mud between all plugs.

1st. plug @ 945' w/25 sx. cement.  
2nd. plug @ 475' w/100 sx. cement w/1 sx. flocele.  
3rd. plug @ 40' w/10 sx. cement.  
15 sx. in rathole (circulated)

Remarks: Allied Cement.

Condition of casing(in hole):GOOD \_\_\_ BAD \_\_\_ Anhy.plug:YES X NO \_\_\_

Bottom plug(in place):YES \_\_\_, CALC \_\_\_, NO \_\_\_ Dakota plug:YES X NO \_\_\_

Plugged through TUBING \_\_\_, CASING \_\_\_. Elevation: 1799 GL

I did [ ] / did not [ X ] observe the plugging.

**INVOICED**

DATE 7-16-93

INV. NO. 3 8127

RECEIVED  
STATE CORPORATION COMMISSION  
07-14-1993  
JUL 4 1993  
Marion J. Schmidt  
Agent)  
CONSERVATION DIVISION  
Wichita, Kansas  
Form CP-2/3