

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22502-00-00
Spot: NWSESW Sec/Twnshp/Rge: 4-11S-15W
1090 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: HACHMEISTER Well Number: 1
County: RUSSELL Total Vertical Depth: 3450 feet

Operator License No.: 31909
Op Name: STULL, JOEL
Address: 404 4TH STREET PO BOX 307
NATOMA, KS 67651

Conductor Pipe: Size feet: 12.13
Surface Casing: Size 8.625 feet: 221 w/145 sxs cmt
Production: Size 4.5 feet: 3449 w/175 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/11/2002 9:00 AM
Plug Co. License No.: 31909 Plug Co. Name: STULL, JOEL
Proposal Rcvd. from: JOEL STULL Company: STULL, JOEL Phone: (785) 885-4222

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 10% gel - 500# hulls - 10 sxs gel.
W.H.M. to 3400'.
Casing squeeze - anhydrite to 420'.

Plugging Proposal Received By: DENNIS HAMEL WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 07/11/2002 11:00 AM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 4 1/2" casing.
Squeezed 25 sxs cement with 200# hulls, followed with 10 sxs gel, followed with 100 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Rigged up cementers to 8 5/8" S.P. - squeezed 25 sxs cement with 100# hulls.
Max. P.S.I. 500#.

RECEIVED
10-17-2002
OCT 17 2002

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Dennis L. Hamel

(TECHNICIAN)

INVOICED

Form CP-2/3

DATE

10-18-02

INV. NO.

2003060667

OCT 08 2002