

8-31

4-060434

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-167-23,069-00-00

SE SW SE /4 SEC. 10, 11 S, 15 W
330 feet from S section line
1650 feet from E section line

Operator license# 5131 Lease Maupin well # 1

Operator: Thunderbird Drilling, Inc. County Russell

Address: P.O. Box 780407 Well total depth 3440 feet
Wichita, Kansas 67278 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 226 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Abercrombie, RTD License# 30634

Address: Wichita, Kansas 67202

Company to plug at: Hour: 10:00A.M Day: 31 Month: August Year: 93

Plugging proposal received from: Gary Fisher

Company: Abercrombie, RTD Phone:

Were: Order 195 sxs. 60/40 posmix - 6% gel with 1/4# flocele per sx.
Space all plugs with heavy drilling mud thru drill pipe.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:00A.M., Day: 31, Month: August, Year: 93

Actual plugging report:
1st. plug at 3385' with 25 sxs. - Arbuckle 3396'.
2nd. plug at 980' with 25 sxs. - Anhydrite 973' - 996'.
3rd. plug at 550' with 80 sxs. - Dakota 251' - 551'.
4th. plug at 280' with 40 sxs. - Surface pipe set at 226'.
5th. plug at 40' with 10 sxs.
Rathole with 15 sxs.

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: 1876 GL

I did / did not [X] observe the plugging.

INVOICED
DATE 9-15-93
BILL NO. 38665

RECEIVED
STATE CORPORATION COMMISSION
09-13-1993
SEP 13 1993
CONSERVATION DIVISION
Wichita, Kansas
[Signature]
(agent)
Form CP-2/3

8-31