

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20885-00-00
Spot: CN2NESW Sec/Twnshp/Rge: 15-11S-15W
2310 feet from S Section Line, 3300 feet from E Section Line
Lease/Unit Name: REICH C Well Number: 1
County: RUSSELL Total Vertical Depth: 3332 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC
Address: 326 MAIN
RUSSELL, KS 67665

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 250 165 SX CMT
Production: Size 5.5 feet: 3328 75 SX CMT
Liner: Size feet: 8108.29

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/20/2001 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/20/2001 11:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded off to 3275' and topped with 5 sxs cement.
Shot casing at 1500' - could not free casing.
Came up to 950' and shot casing - did not free.
Tied onto 5 1/2" and pumped 70 sxs with 300# hulls and displaced to 900'.
Shot casing at 425' - did not free.
Came up to 250' and shot casing free.
Tied onto and circulated cement with 70 sxs.
POOH. Hole full of cement.

RECEIVED

SEP 04 2001
09-04-2001
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 9-4-01

INV. NO. 2002060322

Form CP-2/3

AUG 28 2001