

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-167-22,895-00-00

LEASE NAME Diers

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

4,950 Ft. from S Section Line

990 Ft. from E Section Line

LEASE OPERATOR Leroy E. Tobias

SEC. 4 TWP. 11 RGE. 12 (X) or (W)

ADDRESS HC 69, Box 42, Bunker Hill, Ks. 67626

COUNTY Russell

PHONE#(913) 483-4656 OPERATORS LICENSE NO. 3345

Date Well Completed 4-9-90

Character of Well D & A

Plugging Commenced 4-9-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-9-90

The plugging proposal was approved on 4-9-90 (date)

by Ed Schumacker (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3,270'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	204'	Cmtd. w/140 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Fill hole w/heavy mud. Push bridge plug to 735', spot 20 sax cement on plug thru drill pipe. Push bridge plug to 420', spot 100 sax cement on plug thru drill pipe. Push bridge plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 15 sax down mouse hole.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co., Inc. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Leroy E. Tobias

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec-Treas (Employee of ~~xxxxxxx~~) or ~~xxxxxxx~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec.-Treas.

(Address) Shields Bldg., Russell, KS. 67665

RECEIVED
 STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 16th day of April, 19 90

APR 18 1990
 04-18-1990
 CONSERVATION DIVISION
 My Comm. Expires: _____

NOTARY PUBLIC
 RUTH PHILLIPS
 State of Kansas
 My Appt Exp. 5-26-91

Notary Public