

#4 API NUMBER 15-167-22,063-00-00
 LEASE NAME Strecker

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER #4

3300' Ft. from S Section Line
990' Ft. from E Section Line
 W/2 SE NE
 SEC. 31 TWP. 11 RGE. 12W (E) or (W)

LEASE OPERATOR Shields Oil Producers, Inc.

COUNTY Russell

ADDRESS Shields Bldg. Russell, Kansas 67665

PHONE# (913)483-3141 OPERATORS LICENSE NO. 5184

Date Well Completed _____

Character of Well Oil

Plugging Commenced 6-21-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-24-93

The plugging proposal was approved on _____ (date)

by Hubert Deines (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3270'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	406'	none
				4-1/2"	3137'	2637'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Plugged off bottom with sand to 2915' and 4 sacks cement. Shot pipe @2637', pulled to 1550', pumped 75 sacks cement and 200# hulls, pulled to 760' and pumped 25 sacks cement and 100# hulls, pulled 7 joints and circulated cement to surface, finished pulling pipe. 60/40 pos, 10% gel. Plugging Complete.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Shields Oil Producers, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 8th day of July 1993 RECEIVED
 STATE CORPORATION COMMISSION

Irene Herzberg
 Notary Public

My Commission Expires: _____



JUL - 9 1993
 07-09-1993
 CONSERVATION DIVISION
 Form 608
 Revised 10/88