


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

15-167-00446-00-00  
WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

RUSSELL County. Sec. 33 Twp. 11S Rge. (E) 12 (W)  
Location as "NE/CNW&SW&" or footage from lines. CENTER NW/4 NW/4  
Lease Owner REX & MORRIS DRILLING COMPANY, ET AL  
Lease Name WOODWARD Well No. 1  
Office Address P. O. BOX 334, EL DORADO, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed 27 SEPTEMBER 19 60  
Application for plugging filed 27 SEPTEMBER 19 60  
Application for plugging approved 27 SEPTEMBER 19 60  
Plugging commenced 27 SEPTEMBER 19 60  
Plugging completed 27 SEPTEMBER 19 60  
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production NONE 19      
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well DONALD TRUAN ?  
Producing formation NONE Depth to top      Bottom      Total Depth of Well 3920 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE HOLE	WATER	GROUND L.	264' RB	8 5/8" OD	258.24'	LEFT IN
(SEE ATTACHED LOG)						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

FILLED HOLE WITH DRILLING MUD TO 240', SET PLUG AND CEMENTED WITH 25 SACKS CEMENT, FILLED HOLE WITH MUD TO 40', SET PLUG AND CEMENTED TO SURFACE WITH 10 SACKS CEMENT.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 4 1960  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor REX & MORRIS DRILLING COMPANY  
Address P. O. BOX 334, EL DORADO, KANSAS

STATE OF KANSAS, COUNTY OF BUTLER, ss. A. H. FISHER


(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
P. O. BOX 334, EL DORADO, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 3 OCTOBER day of OCTOBER, 19 60

My Commission expires 8 AUGUST 1962

[Signature]  
ELIZABETH DESCHNER Notary Public.



15-167-00446-00-00

WOODWARD #1

Rex & Morris Drilling Co.  
and  
Rupp-Ferguson Oil Co.  
and  
Cooperative Refinery Association

Total Depth: 3920  
Contractor: Rex & Morris Drilling Co.  
Commenced: 9-16-60  
Completed: 9-27-60  
Initial Prod.: D. & A.

Location: C. NW NW  
Section 33-11S-12W  
Russell County, Kansas

Casing Record:  
8 5/8 @ 264' w/185 Sacks

FORMATION

DEPTH

Surface Hole	264
Shale	730
Anhydrite	770
Shale	1050
Shale and Shells	1360
Lime and Shale	1425
Shale and Lime	1635
Lime and Shale	2160
Shale	2415
Lime and Shale	2735
Lime	2840
Lime and Shale	2979
Lime	3378
Conglomerate	3504
Chat	3532
Lime	3560
Lime and Shale	3619
Lime	3920

T. D.

Ran GR - LL - MLL. Surface casing to T. D.

RECEIVED  
STATE GEOLOGICAL SURVEY  
OCT 4 1960  
10-04-1960  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By Paul D. Koontz  
Paul D. Koontz, Geologist

STATE OF KANSAS  
COUNTY OF BUTLER, ss.

Subscribed and sworn to before me, a Notary Public, this 29th day of September, 1960.

Elizabeth Deschner  
Elizabeth Deschner, Notary Public

My commission expires: August 8, 1962.

