


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Russell County, Sec. 7 Twp. 11 Rge. 14 (E) 14 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE/4 SE/4 SE/4
Lease Owner Time Petroleum Company
Lease Name Thompson Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 16, 1951
Application for plugging filed December 16, 1951
Application for plugging approved December 16, 1951
Plugging commenced December 16, 1951
Plugging completed December 17, 1951
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. E. R. Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3560 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	181'	none
				(circulated Top to Bottom)		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3560 feet to 0 feet for each plug set.

Filled hole with heavy drilling mud to 160'.
Set a bridging plug @ 160'.
Placed 1/2 sack of hulls on top of plug.
Placed 15 sacks of cement on top of hulls.
Filled hole with heavy drilling mud to 40'.
Set a bridging plug @ 40'.
Placed 1/2 sack hulls on top of plug.
Placed 10 sacks of cement on top of hulls to top of hole.

12-26-1951
DEC 26 1951

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Stearns Petroleum, Inc.
Address Box 313, Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*

Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of December, 1951.

My commission expires June 20, 1953
[Signature]
Notary Public.

23-8273-s 4-50-10M

PLUGGING
FILE SEC 7 T 11 R 14 W
BOOK PAGE 133 LINE 4



15-167-00172-00-00

THOMPSON #1

Operator: Time Petroleum Company
Contractor: Stearns Petroleum, Inc.
Commencement Date: December 1, 1951
Completion Date: December 16, 1951

Location: SE/4 SE/4 SE/4, of
Section 7-11S-14W, Russell
County, Kansas.

Casing Record:

8-5/8" 181.58' cemented w/75 sacks.

WELL LOG

Surface Clay	0	34
Sand	34	95
Shale	95	170
Red Bed and Shale	170	300
Blue Shale	300	345
Sand and Shale	345	485
Red Bed & Shale	485	635
Shale	635	804
Anhydrite	804	840
Red Bed and Shale	840	1175
Salt and Shale	1175	1465
Shale and Shells	1465	1785
Shale and Lime	1785	2932
<u>Lansing Kansas City</u>	2932	3210
<u>Lime and Shale</u>	3210	3294
<u>Conglomerate</u>	3294	3317
<u>Lime</u>	3317	3355
<u>Conglomerate</u>	3355	3372
<u>Viola Lime</u>	3372	3490
<u>Simpson</u>	3490	3506
<u>Arbuckle</u>	3506	3560
<u>Total Depth</u>	3560	

STATE OF KANSAS)
COUNTY OF RUSSELL) SS

I hereby certify that the above information is true and correct to the best of my knowledge.

B. Stearns

SUBSCRIBED AND SWORN to before me this 22nd day of December, 1951.



1226-1951

Harold H. Lebon
Notary Public

My Commission Expires: June 20, 1953

FILE SEC-7 11-14W
BOOK PAGE 133-9