


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

### WELL PLUGGING RECORD

Russell County. Sec. 14 Twp. 11 Rge. 15 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SW  
Lease Owner B & R DRILLING, INC.  
Lease Name MILLER Well No. 1  
Office Address RUSSELL, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed October 20, 1950 19  
Application for plugging filed October 19, 1950 Verb. 19  
Application for plugging approved October 19, 1950 " 19  
Plugging commenced October 20, 1950 19  
Plugging completed October 20, 1950 19  
Reason for abandonment of well or producing formation DRY HOLE

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation Depth to top Bottom Total Depth of Well 3400 Feet  
Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8 "	216'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

#### Plugging Record.

Filled hole with heavy mud to 210 feet. Wooden plug @ 210. Mix 15 sacks cement in barrel and pour through drill pipe (210)- Fill hole to 35 feet. Wooden plug @ 35 feet tied to surface pipe. 1/2 sack hull on plug and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R DRILLING, INC.  
Address RUSSELL, KANSAS

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
DON ROBERTS (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *[Signature]*

Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of November, 1950

My commission expires 6-17-54

PLUGGING 23-8273-S 4-50-10M  
 FILE SEC 14 T 11 R 15  
 BOOK PAGE 38 LINE 6

*[Signature]*  
 Notary Public.  
 11-07-1950  
 NOV 7 - 1950  
 CONSERVATION DIVISION  
 Wichita, Kansas

B & R DRILLING, INC.  
MILLER # 1

SW SW SW Sec. 14-118-15W  
RUSSELL COUNTY, KANSAS

Total Depth: 3400'  
Comm: 10-7-50  
Comp: 10-20-50

Casing

Cement

8 5/8" Set @ 216'

140 Sacks of Lone Star

Formation-	Depth
Shale-Shells	216
Shale	360
Shale-Sand Hard	662
Shale	730
Shale-Shells	765
Anhydrite	798
Sand Iron	820
Shale-Shells-RedBed	943
Anhydrite	965
Anhydrite	978
Shale	1335
Shale-Shells	1612
Shale-Lime	2610
Lime	2630
Lime-Shale	2785
Lime	2845
Lime-Shale	2890
Lime	2915
Lime-Shale	2990
Lime	3338 $\frac{1}{2}$
Conglomerate	3364
Sand	3372
Lime-Shale	3385
Conglomerate	3400'

STATE OF KANSAS)  
                                  )SS  
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

*Violet Keller*

Subscribed and sworn to before me this 6th day of November, 1950

*Clara Hummel*  
Notary Public

My commission expires: 6-17-54

11-07-1950

FILED  
11-11-1950  
38  
6