


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Russell County. Sec. 6 Twp. 11 Rge. (E) 15 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW/4 SW/4 SW/4
Lease Owner F. W. Kramer, et al.
Lease Name Kramer Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 6, 19 51
Application for plugging filed June 6, 19 51
Application for plugging approved June 7, 19 51
Plugging commenced June 6, 19 51
Plugging completed June 7, 19 51
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3570 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	183'	none
				(circulated)		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3570 to 170.
Set a bridge at 170.
Placed 15 sacks of cement on top of bridge.
Filled hole with heavy mud to 40 feet.
Set a bridging plug at 40 feet.
Put 1/2 sack hulls on top of plug.
Run 10 sacks of cement from plug to top of hole.

RECEIVED
STATE CORPORATION COMMISSION
06-11-1951
JUN 11 1951
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Stearns Petroleum, Inc.
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
O. G. Stearns (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *O. G. Stearns*

Russell, Kansas (Address)



Harold H. Housh
Notary Public

My commission expires June 20, 1953.

PLUGGING
JUN 6 6 11 1951
JUN 8 7 1951

15-167-00152-00-00

KRAMER #1

Operator: Stearns Petroleum, Inc.
Contractor: Stearns Petroleum, Inc.
Commencement Date: 5-24-51
Completion Date: 6-7-51

Location: SW/4 SW/4 SW/4,
6-11-15, Russell County, Kansas.

Elevation: 1908' D.F.

Casing Record:
8-5/8" 180'

Tops:
Kansas City 3115'
Arbuckle 3546'

WELL LOG

clay and shale	0	130
blue shale	130	180
shale and shells	180	355
sand	355	600
shale and red bed	600	1080
<u>Anhydrite</u>	1080	1122
shale and shells	1122	1490
sand	1490	1625
shale and shells	1625	1760
lime and shale	1760	2215
shale and shells	2215	2295
lime and shale	2295	3115
lime	3115	3268
lime and shale	3268	3315
lime	3315	3451
conglomerate	3451	3546
lime	3546	3570
<u>Total Depth</u>		3570

STATE OF KANSAS)
COUNTY OF RUSSELL) SS

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1951
CONNECTION DIVISION
Wichita, Kansas

I hereby certify that the above information is true and correct to the best of my knowledge.

[Signature]

SUBSCRIBED AND SWORN to before me this 9th day of June, 1951.



PLUGGING
FILE SEC 6-T-11-R-154
BOOK PAGE 87 LINE 15

[Signature]
Notary Public

My Commission Expires: June 20, 1953.