


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Russell County. Sec. Twp. Rge. (E) (W)



Locate well correctly on above Section Flat

Location as "NE/CNW%SW%" or footage from lines _____
 Lease Owner Western Development Company
 Lease Name Worley Well No. 1
 Office Address Box 1201, Santa Fe, New Mexico
 Character of Well (completed as Oil, Gas or Dry Hole) _____
 Date well completed _____ 19____
 Application for plugging filed _____ 19____
 Application for plugging approved _____ 19____
 Plugging commenced 3-22- 1955
 Plugging completed 3-29- 1955
 Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner, State Pluggger, Russell County
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1955
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole from 3368' to 3180' - ran 5 sacks cement - mudded hole to 240' - set 10' rock bridge - ran 20-sacks cement --mudded hole on up to 50' - set 10' rock bridge - ran 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company
 Address Ellinwood, Kansas

STATE OF NEW MEXICO, COUNTY OF SANTA FE
Zane E. Henderson, Sec'y, Western Development Company of Delaware, owner
 (employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Zane E. Henderson
Western Development Company of Delaware
P.O. Box 1201 (Address) Santa Fe, N.M.

SUBSCRIBED AND SWORN TO before me this 11th day of April, 1955
Barbara F. Neulist

My commission expires 2/8/58



PLUGGING
FILE SEC 4 T 11 R 15
BOOK PAGE 106 LINE 14

15-167-00286-00-00

OPERATOR: WESTERN DEVELOPMENT CO.
P. O. Box 1201
Santa Fe, New Mexico

CONTRACTOR: MAST DRILLING, INC.
Russell, Kansas

LEASE: Worley No. 1
NW/4 NW/4 NE/4
Sec. 4, T. 11S, R. 15W
Russell County, Kansas

COMMENCED: 12- 5-54

COMPLETED: 12-21-54

FORMATION	DEPTH
Shale and Clay	210
Sand	240
Shale and Sand	265
Sand	350
Shale-Blue	550
Sand and Shale	665
Shale-Shells	942
Red Bed	975
Anhydrite	1014
Red Bed	1240
Shale-Shells	1655
Shale-Lime	2330
Shale-Shells	2600
Shale-Lime	2902
Lime	2930
Coring	3026
Reaming	3026
Lime	3040
Coring	3078
Reaming	3078
Shale-Lime	3103
Coring	3127
Lime	3135
Lime	3360
Chert	3369
Congl. TOTAL DEPTH	3421

I hereby certify that the above is true and correct to the best of my knowledge.

James J. Thomas

STATE OF KANSAS)
)ss
COUNTY OF RUSSELL)

Subscribed and sworn to before me this 22 day of December, 1954.

Betty Jean Holyard
Notary Public

My Commission Expires: 8-9-58

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1955
03-22-1955
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 4 T 11 R 15W
BOOK PAGE 106 LINE 14