

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

15-167-00416-00-00
WELL PLUGGING RECORD

Russell County, Sec. 15 Twp. 11 Rge. 15 (E) (W)

Location as "NE/CNW/SW" or footage from lines C SE NW

Lease Owner Okmar Oil Company

Lease Name Reich Well No. 1

Office Address 820 Union National Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed June 4 19 61

Application for plugging filed September 18 19 61

Application for plugging approved September 21 19 61

Plugging commenced November 8 19 61

Plugging completed November 10 19 61

Reason for abandonment of well or producing formation not commercial production

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Donald Truan

Producing formation Depth to top Bottom Total Depth of Well 3355 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	174	-
				5-1/2	3346	2609

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Cleaned out cellar and rigged up, filled with sand from 3355' to 3350' run 4 sacks of cement from 3350' to 3320'. Worked 20" tension in 5 1/2" pipe shot at 2691', 2595' and started 5 1/2" pipe. Had 80 sacks of cement and 10 sacks of mud pumped in 8-5/8" to plug well.

RECEIVED
STATE CORP. COMMISSION
NOV 22 1961
11-22-1961
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address P. O. Box 114, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Robert M. Beren (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
820 Union National Bldg., Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 21st day of November, 19 61

My commission expires November 16, 1965
Wanona Duff
Notary Public.



DRILLER'S LOG

15-167-00416-00-00

COMPANY: OKMAR OIL COMPANY
CONTRACTOR: LEBEN DRILLING, INC.
FARM: RIECH #1
LOCATION: C SE NW, Sec. 15-11S-19W
 RUSSELL COUNTY, KANSAS
COMMENCED: 5-26-61
COMPLETED: 6-4-61

0	20	Surface Clay
20	100	Shale & Sand
100	135	Shale
135	178	Shale & Shells
178	900	Shale, Sand & Shells
900	955	Shale
955	980	Anhydrite
980	1485	Shale
1485	1625	Shale & Shells
1625	1750	Lime & Shale
1750	1930	Shale & Lime
1930	2120	Lime
2120	2180	Lime
2180	2340	Shale & Lime
2340	2590	Shale & Lime
2590	2765	Shale & Lime
2765	2880	Lime
2880	2950	Lime
2950	3010	Lime
3010	3035	Lime
3035	3070	Lime
3070	3088	Lime
3088	3150	Lime
3150	3210	Lime
3210	3215	Lime
3215	3255	Lime
3255	3325	Lime
3325	3345	Lime
3345	3355	Lime
	3355	ROTARY TOTAL DEPTH

RECEIVED
 CONSERVATION COMMISSION
 SEP 19 1961
 09-19-1961
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" casing at 171' with 150 sacks Sunset Cement.

Set 5 1/2" new casing at 3346' with 125 sacks common cement.

I, Theodore I. Leben, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Riech, located C SE NW, Section 15, Township 11S, Range 15W, Russell County, Kansas as reflected by the files of Leben Drilling, Inc.


 Theodore I. Leben

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 16th day of June, 1961.

My commission expires:
April 10, 1965


 Wanda Kiker, Notary Public

