

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1974

CONSERVATION DIVISION
Wichita, KansasVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas,

Lease Name: Albertson Well No. 1

Location: SE-SE-SW Sec. 18 Twp. 9 Rge. (E)(W) 26

County: Graham Total Depth 3953' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

168'--8 5/8" Surface casing, cement circulated with 125 Sx.
Top of Dakota section @ 735'.

Circulate hole with heavy mud. Pull DP to 960' and displace 110 Cu. Ft. cement thru DP. Pull DP to 185' and displace 30 Cu Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. G. Nichols
Conservation Division Agent