

State of Kansas



CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSIONAPR 12 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. George Sowles of A. L. Abercrombie, Inc., has this
date requested permission to plug the following described well:Mr. Sowles guarantees payment of the plugging fee.Operator's full Name: A. L. Abercrombie, Incorporated,Complete Address: 801 Union Center Building, Wichita, Kansas.Lease Name: Ernst Well No. 1Location: SW-NE-SW Sec. 20 Twp. 9 Rge. (E)(W) 23County: Graham Total Depth 3985' Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Sowles was instructed to plug the well as follows:260'--~~2-1/2~~"^{7" OD} Surface casing, cement circulated. (6 1/4" Hole).3984'--4 1/2" Production casing cemented on bottom with 125 Sx. Well
plugged back to 3955'. Top perforations from 3795' to 3798'.Sand well back to 3725' and set 3 Sx. cement with dump bailer. Pull
4 1/2" casing and squeeze well with 3 sacks hulls, 15 sacks gel and 110'
Sx. cement, staged.

Very truly yours,

Conservation Division Agent