

15-065-20664-0000

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 3 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Reiter of Murfin Drlg. has this

date requested permission to plug the following described well:

Mr. Reiter guarantees payment of the plugging fee.

Operator's full Name: Zetco Petroleum Co., Inc.

Complete Address: 357 Lulu, Wichita, Ks.

Lease Name: Ernst Well No. 1

Location: S/2 SE NW Sec. 20 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3930' Oil Well     

Gas Well      Input Well      SWD Well      D & A XX Lost Hole     

Mr. Reiter was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 900' & displace

70 sk cmt thru drill pipe. Heavy mud to 240' & displace 20 sk cmt

thru drill pipe. Heavy mud to 40' build ~~bed~~ bridge & 10 sk cmt to

base of cellar.

Very truly yours,

Leo Massey  
Conservation Division Agent