



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

APR 12 1971

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. George Sowles of A. L. Abercrombie, Inc., has this date requested permission to plug the following described well:

Mr. Sowles guarantees payment of the plugging fee.

Operator's full Name: A. L. Abercrombie, Incorporated,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Ernst Well No. 2

Location: CN/2-SW-SW Sec. 20 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 4000' Oil Well

Gas Well  Input Well  SWD Well X D & A  Lost Hole

Mr. Sowles was instructed to plug the well as follows:

7" DD.  
256' - ~~8 5/8"~~ Surface casing, cement circulated with 80 Sx.  
2065' - ~~4 1/2"~~ Casing cemented with 250 Sx. Top of Cement @ 825' (Temperature Survey). Perforations from 1544' to 1780'.

Push plug to 1500', sand back to 1475' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 3 sacks hulls, 15 sacks gel and 110 Ex. cement, staged.

Very truly yours,

Conservation Division Agent