

State of Kansas



JOHN ANDERSON, Jr. Governor
 WILLIAM L. MITCHELL, Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

JUL 19 1965

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co has this

date requested permission to plug the following described well:
Burch Explor., Ltd.,

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Burch Exploration, limited,

Complete Address: 1011 Union Center, Wichita, Kansas.

Lease Name: Hildebrand Well No. 1

Location: SE-SE-SW Sec. 21 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3925 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

208' -- 8 5/8" Surface pipe, cement circulated with 145 Sx.
3920' -- 5 1/2" Production string cemented with 150 Sx. and Kem-Pac
from Dakotas to surface. Well plugged back to 3875.

Sand back to 3730 and set 5 Sx. cement with dump bailer.

Pull 5 1/8" to 540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2"

to 210' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set rock
bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. D. Nichols
 Conservation Division Agent