

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
1-19-66  
JAN 19 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Co. has this

date requested permission to plug the following described well:

Specter Pipe & Supply  
Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe and Supply,

Complete Address: Box # 169, Russell, Kansas.

Lease Name: Prescott Well No. 1

Location: SW-SW-SE Sec. 21 Twp. 9 Rge. (E)(W) 23

County Graham Total Depth 3975 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Lynch was instructed to plug the well as follows:

1375' -- 8 5/8" Surface pipe, cement circulated,  
3972' -- 5 1/2" Production casing cemented with 150 Sx. Top of  
cement @ 3425' (Temperature Survey) No plug back or perforations.

Sand well back to 3965' and set 5 Sx. cement with dump bailer.  
Set bridge @ 550' and 20 Sx. cement. Mud to 250', set bridge  
@ 250' and 20 Sx. cement. Mud to 40', set bridge and 10 Sx.  
cement to bottom of cellar.

Very truly yours,

R. L. Nichols  
Conservation Division Agent