

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
5-23-66
MAY 23 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Walter Voth of Knight Casing Pulling Co has this date requested permission to plug the following described well:
Leben Drilling, Inc.
Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling, Incorporated,

Complete Address: 815 Wichita Plaza, Wichita, Kansas.

Lease Name: LaCerte Well No. 2

Location: CSE-NW Sec. 25 Twp. 9 Rge. (E) (W) 25

County Graham Total Depth 3950 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

211'--8 5/8" Surface pipe, cement circulated.
3921'--4 1/2" Production casing cemented with 100 Sx. Top perforations @ 3872'.

Sand well back to 3850' and set 3 Sx. cement with dump bailer.
Pull 4 1/2" to 600' and circulate heavy gel mud, Pull 4 1/2" to 540' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 240' and displace 20 Sx. cement thru 4 1/2" Pull 4 1/2", set rock bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. L. Nichols
Conservation Division Agent