

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Jim Beakey of Santa Fe Pipe & Supply, has this

date requested permission to plug the following described well:

Woodman & Iannitti Oil Co.,

Mr. Beakey guarantees payment of the plugging fee.

Operator's full Name: Woodman and Iannitti Oil Company.,

Complete Address: 706 Union National Bldg., Wichita, Kansas.

Lease Name: Lacerte Well No. 1

Location: CS/2-SW-SW Sec. 25 Twp. 9 Rge. (E)(W) 23

County Graham Total Depth 3924 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Beakey was instructed to plug the well as follows:

181'--8 5/8" Surface pipe, cement circulated with.

3924'--5 1/2" Production casing cemented with 100 Sx. Well plugged back to 3905'. Top perforations @ 3732'.

Push plug to 3680', sand back 25' and set 5 Sx. cement with dump bailer. Set bridge @ 400' and fill hole with Redi-Mix cement.

Very truly yours,

W. L. Nichol
Conservation Division Agent