

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 FEB 20 1963  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Earl Dunlap of C & G Drilling Co has this

date requested permission to plug the following described well:

D. G. Hansen

Mr. Dunlap guarantees payment of the plugging fee.

Operator's full Name: D. G. Hansen

Complete Address: Logan, Kansas.

Lease Name: Sparks Well No. 3

Location: SE-SE-SW Sec. 26 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3915 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dunlap was instructed to plug the well as follows:

196' 8 5/8" surface, cement circulated.

Circulate hole with heavy mud, set plug @ 540' w/20 Sx cement.

" " 180' w/20 Sx cement.

" " 40' w/10 Sx cement & 1/2 SK Halls.

Very truly yours,

W. L. Nichols  
 Conservation Division Agent