

15-065-20144-0000

State of Kansas



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 27 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Paul Stevens of Omega Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Stevens guarantees payment of the plugging fee.

Operator's full Name: McKnab Production Company, Incorporated,

Complete Address: 1028 Midland Savings Bank Building, Denver, Colo.

Lease Name: KANSAS STATE UNIVERSITY Endowment Association Well No. 1

Location: N/2-N/2-NW/4 Sec. 26 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3705 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stevens was instructed to plug the well as follows:

210'--8 5/8" Surface pipe, cement circulated with 170 Sx.
Top of Dakota Section @ 825.

Circulate hole with heavy mud. Pull DP to 1050' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set plug with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

Very truly yours,

W. B. Dickel
 Conservation Division Agent