

API NUMBER 15-065-22,456 - 0006

LEASE NAME Lacerte

WELL NUMBER #1

330 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 25 TWP. 9 RGE. 23 XX or (W)

COUNTY Graham

Date Well Completed 10-24-88

Plugging Commenced 5-20-94

Plugging Completed 5-20-94

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Davis Petroleum, Inc.

ADDRESS R.R. 1 Box 183 B Great Bend, Ks. 67530

PHONE# (316) 793-3051 OPERATORS LICENSE NO. 4656

Character of Well oil

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on May 17, 1994 (date)

by Dennis Hemel (dist) David P. Williams (wichita) (KCC District Agent's Name).

Is ACC-1 filed? yes If not, is well log attached? no

Producing Formation Lansing Depth to Top _____ Bottom _____ T.O. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
surface		.0	268'	8 5/8"	268'	none
production		0	3898	5 1/2"	3898'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from ___ feet to ___ feet each set

Dug out so could pressure up backside & pump down it. Perf. anhy @ 1975-1977 by Wire-Tech Pressured 8 5/8" to 600 psi mixed 50 sx w/2 hulls followed W/10 gel, followed W/170 sx & 3 hulls Total: 200 sx. 60/40 poz, 10% gel and 5 hulls.

Name of Plugging Contractor Allied Cementing License No. _____

Address P.O. Bpx 31 Russell, Kansas 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Davis Petroleum, Inc.

STATE OF Kansas COUNTY OF Barton, ss.

L. D. Davis

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.


(Signature) L. D. Davis

(Address) R.R. 1 Box 183 B Great Bend, Ks 67530

SUBSCRIBED AND SWORN TO before me this 16th day of August, 19 94

My Commission Expires: 5-20-97

Notary Public
Bessie M. DeWerff



RECEIVED
 STATE CORPORATION COMMISSION
 8-17-94
 AUG 17 1994

CONFIRMATION DIVISION
 WICHITA, KANSAS