

15-065-30117-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 25 Twp. 9 Rge. 23 (E) W (W)  
Location as "NE/CNW%SW%" or footage from lines 150' NE of C SE NW  
Lease Owner Leben Drilling Company  
Lease Name Lacerte Well No. 2  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 5-13-66 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 5-19-66 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3950 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	211'	None
				4-1/2"	3921'	2479'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3950', sanded hole to 3850' and dumped 5 sacks of cement @ 3850' with dump bailer. Pulled 4 1/2" casing to 600' and pumped in 16 sacks of gel mud. Pulled 4 1/2" casing to 540' and pumped in 20 sacks of cement. Pulled 4 1/2" casing to 240' and pumped in 20 sacks of cement. Pulled balance of 4 1/2" casing, bailed hole to 35', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

6-2-66  
JUN - 2 1966

PLUGGING COMPLETE.

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 19 66

My commission expires May 20, 1968

Milton J. Volin  
Notary Public.

DRILLER'S LOG

COMPANY: Leben Drilling, Inc.  
 CONTRACTOR: LEBEN DRILLING, INC.  
 FARM: LACERTE #2  
 LOCATION: C SE NW Sec. 25-9S-23W  
 GRAHAM COUNTY, KANSAS  
 COMMENCED: 7-11-65  
 COMPLETED: 7-20-65

0	211	Clay & Blue Shale
211	675	Shale
675	1675	Sand & Shale
1675	1990	Shale
1990	2025	Anhydrite
2025	2078	Shale
2078	2450	Shale & Shells
2450	3613	Shale & Lime
3613	3716	Lime & Shale
3716	3950	Lime
	<u>3950</u>	<u>RTD - Set 4 1/2" Casing</u>

Set 8 5/8" used surface casing @ 211' with 175 sacks 60-40  
 Posmix Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Lacerte #2 well located C SE NW of Section 25, Township 9 South, Range 23 West, Graham County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
 Leslie Kite

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BARTON )

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 21st day of July, 1965.

Ulanda Nichols  
 Ulanda Nichols

My Commission Expires:  
 April 1, 1967

**RECEIVED**  
 STATE CORPORATION COMMISSION

JUN -2 1966

CONSERVATION DIVISION  
 Wichita, Kansas