


15-065-00740-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

GRAHAM County. Sec. 25 Twp. 9 Rge. 23 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner EMPIRE DRILLING COMPANY
Lease Name LACERTE Well No. 1
Office Address 407 BROWN BUILDING, WICHITA 2, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed 3-28-55 19
Application for plugging filed MARCH 28 19 55
Application for plugging approved MARCH 28 19 55
Plugging commenced MARCH 28 19 55
Plugging completed MARCH 28 19 55
Reason for abandonment of well or producing formation DRY HOLE

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4200 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SURFACE		0	192'	8 5/8"	192'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FIRST PLUG AT 185' - 1/2 SACK HULLS AND 15 SACKS CEMENT.
TOP PLUG AT 40' - 1/2 SACK HULLS AND 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor EMPIRE DRILLING COMPANY
Address 407 BROWN BUILDING, WICHITA 2, KANSAS.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
I, DAN J. KORNFELD (employee of owner) (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dan J. Kornfeld
DAN J. KORNFELD
EMPIRE DRILLING COMPANY, 407 BROWN BLDG.,
(Address) WICHITA, KANSAS

SUBSCRIBED AND SWORN to before me this 31st day of MARCH, 1955.

My commission expires DECEMBER 10, 1956 Notary Public.

PLUGGING
FILE SEC 25 T 9 R 23W
BOOK PAGE 108 LINE 26

RECEIVED
4-2-55
CONSERVATION DIVISION
WICHITA, KANSAS

L O G

COMPANY: EMPIRE DRILLING COMPANY
 CONTRACTOR: EMPIRE DRILLING COMPANY
 FARM: LACERTE #1
 LOCATION: NW NW SE SEC. 25-9-23
 GRAHAM COUNTY, KANSAS
 COMMENCED: 3-16-55
 COMPLETED: 3-28-55

0	TO	1730	SAND AND SHALE
1730	TO	1985	SHALE AND SHELLS
1985	TO	2018	ANHYDRITE
2018	TO	2300	SHALE
2300	TO	2460	SHALE AND SHELLS
2460	TO	2645	SHALE AND LIME STREAKS
2645	TO	3125	LIME AND SHALE
3125	TO	3205	LIME
3205	TO	3315	LIME AND SHALE
3315	TO	4050	LIME
4050	TO	4100	SHALE AND LIME
4100	TO	4200	LIME
4200			R.T.D.

SET 192' OF 8 5/8" SURFACE CASING, CEMENTED WITH 115 SACKS OF CEMENT.

ELEVATION: 2407 K.B.

TOPS: ANHYDRITE 1984'; HEEBNER 3668'; TORONTO 3688'; K.C. 3703'. R.T.D. 4200'.

D.S.T. #1 3851' TO 3871'; D.S.T. #2 3871 TO 3895'; D.S.T. #3 3895' TO 3920';
 D.S.T. #4 4088' TO 4120'.

D & A

C E R T I F I C A T I O N


I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE LACERTE #1, NW NW SE, SECTION 25, TOWNSHIP 9 SOUTH, RANGE 23 WEST, GRAHAM COUNTY, KANSAS, AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS, THIS 31ST DAY OF MARCH, 1955.

MY COMMISSION EXPIRES DECEMBER 10, 1956.

E. W. ...
 NOTARY PUBLIC



PLUGGING
 25-9-23W
 108 26

RECEIVED
 STATE OF KANSAS
 CONSERVATION DEPARTMENT
 (Wichita, Kansas)