


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Graham County. Sec. 28 Twp. 9S Rge. 23W (E) (W)
Location as "NE/CNW*SW*" or footage from lines NW SW NW
Lease Owner Burch Drilling Co., Inc.
Lease Name Morris Well No. 7
Office Address 1011 Union Center - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed 1-13 1958
Application for plugging filed 1-13 1958
Application for plugging approved 1-13 1958
Plugging commenced 1-13 1958
Plugging completed 1-13 1958
Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4035 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	226	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 500' w/25 sx.
Set 2nd plug @ 200' w/15 sx.
Set 3rd plug @ 40' w/10 sx.

RECEIVED
STATE CORPORATION COMMISSION
1-17-58
JAN 17 1958
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Burch Drilling Co., Inc.
Address 1011 Union Center - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Earl M. Burch (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl M Burch

(Address) _____
SUBSCRIBED AND SWORN TO before me this 16th day of Jan., 19 58.

Betty Spriggs Notary Public.

My commission expires 6-13-59.

PLUGGING
FILE SEC 28T 9 R.234
BOOK PAGE 77 LINE 14

WELL LOG

Burch Drilling Co., Inc.
#7 Morris
NW SW NW 28-9-23W.
Graham County, Kansas

Comm: 1-6-58
Comp: 1-13-58
8 5/8" @ 226' w/165 sx.
Elevation: 2463 KB
RTD 4035
D & A

226 Clay & Soil
1375 Shale & Shells
2056 Shale & Lime streaks
2105 Anhydrite
3840 Shale & Lime
4035 Lime

4035 RTD

Tops:
Heebner 3756
Toronto 3781
Lansing 3794

DST #1 3818-40 1 hr. Rec.
6' mud. BHP 67#.
DST #2 3858-70 1 hr. Rec.
27' mud. BHP 730#.
DST #3 3916-40 1 hr. Rec.
6' mud. BHP 40#.
DST #4 3940-80 1 hr. Rec.
10' mud. BHP 75#.

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1958

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
SEC 28 T 9 R 23 W
BOOK PAGE 77 LINE 14

STATE OF KANSAS; COUNTY OF SEDGWICK: ss:

Earl M. Burch, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed and that the same are true and correct.

Earl M. Burch
Earl M. Burch

Subscribed and sworn to before me this 16th day of January, 1958.

Betty Spriggs
Notary Public