

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

#6 15-065-01558-0000

API NUMBER June 29, 1957

LEASE NAME Morris

WELL NUMBER 2

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

3630 ^{RTKCC} ~~650~~ Ft. from S Section Line

3630 ~~660~~ Ft. from E Section Line

SEC. 28 TWP. 9 RGE. 23 (E) or (W)

COUNTY Graham

Date Well Completed 6-29-57

Plugging Commenced 5-1-87

Plugging Completed 5-1-87

LEASE OPERATOR Burch Exploration Inc.

ADDRESS 11190 Cambridge Court, Parker, CO 80134

PHONE# (303) 841-9417 OPERATORS LICENSE NO. 7448

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? Yes

Producing Formation Lansing K.C. Depth to Top 3768 Bottom 3992 T.D. 4030

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Shale		Surface	208	8 5/8		None
Lansing		Surface	402	9 5 1/2		None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Call state plugger, Carl Goodrow. Mix 300 lbs of hulls with first 30 sks of cement. Fill 5 1/2 to surface 125 sks total. Mix 200 lbs of hull to 20 sks of cement. Pump down 8 5/8 casing. Fill to surface pressure to 200 lbs. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Poe's Well Service License No. 6779

Address P.O. Box 115, Oberlin


STATE OF Kansas COUNTY OF Decatur, ss.

Melvin L. Taylor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Melvin L. Taylor

(Address) 405 E. 14th St., McCook, NE 69001

SUBSCRIBED AND SWORN TO before me this 22 day of MAY, 1987



My Comm. 5340

Larry S. Eisenmenger
 Notary Public
 RECEIVED
 STATE CORPORATION COMMISSION
 5-26-87

MAY 23 1987