



15-1065-20327-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1970

CONSERVATION DIVISION
Wichita, Kansas

5-25-70

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: James P. Simmons-National Oil Company,

Complete Address: 200 West Douglas, Wichita, Kansas.

Lease Name: Riffel Well No. 1

Location: SE-SE-NW Sec. 27 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3920' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ulrich was instructed to plug the well as follows:

203'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 825'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.
Pull DP, set plug @ 40' with 1/2 sack hulls and 16 Sx. cement to bottom
of cellar.

Very truly yours,

A. J. Dicks
Conservation Division Agent