



15-065-20325-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1970
CONSERVATION DIVISION
Wichita, Kansas

5-19-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drilling Company, has this
date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: National Oil Company,

Complete Address: Suite 550, O. W. Garvey Building, Wichita, Kansas.

Lease Name: Law Well No. 1

Location: NW-NW-SE Sec. 27 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ulrich was instructed to plug the well as follows:

208'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 850'.

Circulate hole with heavy mud. Pull DP to 1050' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent