



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
NOV 19 1965  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Hale Oller of Murphy Drilling Co. has this

date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Murphy Drilling Co.

Complete Address: 617 Union East - Wichita Kansas

Lease Name: Chesney #1 Well No. 1

Location: Sw - Se - New Sec. 5 Twp. 11 Rge. 16 (E)(W)

County Ellis Total Depth 3562 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Oller was instructed to plug the well as follows:

Jett pits circulate hole with heavy mud, set cementing plug at 540 ft  
and displaced 20 sac cement thru drill pipe, heavy mud to 50 ft., set  
cementing plug and displace 20 sac cement, heavy mud to 40 ft., set  
cementing plug, 1/2 sac hulls and 10 sac cement, cementing to base of cellar.

Very truly yours,

Gilbert P. Leiker

Conservation Division Agent