



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
12-6-1968
DEC 6 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Weiler of Shields Drlg. has this

date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Prospect Oil & Shields Drlg.

Complete Address: 811 Union Center Wichita, Ks.

Lease Name: Bowlby Well No. 1

Location: NE NE SE Sec. 23 Twp. 11 Rge. 16 (E)(W) X

County: Ellis Total Depth 3061 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weiler was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace
50 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Conservation Division Agent