



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 8-26-1968
 AUG 26 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Landis of Kern Drlg. has this

date requested permission to plug the following described well:

Mr. Landis guarantees payment of the plugging fee.

Operator's full Name: Kern Drlg. Co., Inc.

Complete Address: Box 638 Magnolia, Arkansas

Lease Name: Chrisler Well No. 1

Location: NE NW NW Sec. 25 Twp. 11 Rge. 16 (E)(W) X

County: Ellis Total Depth 3469 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Landis was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 450' and displace

70 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and

displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

Very truly yours,

Les F. Massey
 Conservation Division Agent